

Gram : CENBOSEC, Delhi – 92
E-Mail: cbseedi@nda.vsnl.net.in
website: www.cbse.nic.in



Phone: 22509256-59
Fax: 22515826

CENTRAL BOARD OF SECONDARY EDUCATION

(An Autonomous Organisation under the Union Ministry of Human Resource Development Govt. of India)

“SHIKSHA KENDRA”, 2, COMMUNITY CENTRE, PREET VIHAR, DELHI – 110092

F-1/129/09/TW/SQ/2013

Dt. 07.03.2013

.....
.....
.....
.....

Sub: Limited Tender for Tile work at CBSE Staff Qtrs.

Sir,

The Board intends to provide tiling work in floor & staircase in its inhabited staff qtrs. at Brij Vihar (GZB) for which Limited Tenders are invited from the agencies having at least 5 years experience & executed minimum 3 works of equivalent magnitude. The rates are to be applied on the prescribed format annexed herewith. An EMD of Rs. 2000/- in the form of DD/BD payable to the Secretary, CBSE is to be annexed with the tender. Experience documents also be attached alongwith the tender. Sealed tenders complete in all respect must be submitted on or before 16.03.2013 upto 02:30 P.M. Tenders which are either late or incomplete shall be summarily rejected. The Secretary, CBSE reserves the right to reject any or all the tenders without assigning any reason thereof.

Yours faithfully

(S.K. SHARMA)

Superintending Engineer

SCHEDULE OF WORK

Last date : 16.03.2013 upto 2.30 p.m.

Name of Work: Tile work at CBSE Staff Qtrs. Brij vihar (GZB)

S.No.	Description	Qty.	Unit	Rate	Amount
1.	<p>Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps after proper hacking of the existing mosaic flooring at 100mm centre to centre thereafter laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints with white cement & matching pigment etc. complete.</p> <p>Size of Tile 600x600 mm</p> <p>Note: The cost of tiles shall be in the range of Rs. 70-75 per sq. ft.</p>	15.0	Sqm		
2.	<p>Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622 , of approved brand & manufacturer, in all colours and shade, after proper hacking of the existing mosaic flooring at 100mm centre to centre thereafter laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints with white cement & matching pigment etc. complete.</p> <p>Size of Tile 600x600 mm</p> <p>Note: The cost of tiles shall be in the range of Rs 70-75 per sq. ft.</p>	120	Sqm		

3.	<p>Providing and laying antiskid Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except white, ivory, grey, fume red brown on the existing flooring after proper hacking of the existing flooring at 100mm centre to centre thereafter laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints with white cement & matching pigment etc. complete.</p> <p>Note: The cost of tiles shall be in the range of Rs. 42-45 per sq. ft.</p>	23	Sqm		

Signature of the Agency with

Complete address and seal

Telephone_____

Mobile No._____

Terms & Conditions

1. The work shall be executed as per the approved specifications and CPWD norms.
2. The work is time bound, hence time is the essence of the contract.
3. The work is to be completed within 10 days from the date of work order.
4. All the materials shall be got approved from the Engineer Incharge before procurement & installation.
5. The vitrified tiles & antiskid tiles shall be of reputed brand namely Kajaria, Somani, Orient, Nitco.
6. No T & P shall be provided by the Board.
7. Scaffolding shall be arranged by the Contractor.
8. The work shall be executed under the strict supervision of the Board's J.E/ S.E.
9. The measurements shall be recorded jointly.
10. Potable water shall only be used, in no case ground water shall be used.
11. In case of delay, a penalty @ 1% per week shall be levied subject to a max of 5%.
12. In case of poor workmanship, the Board shall have the right to rescind the contract and get the work executed through any other agency at the risk & cost of the defaulting contractor.
13. In case the work is kept suspended without any valid reason, the Board shall be free to get the remaining work executed through any other agency.
14. The contractor shall be required to provide adequate safety for its workers and the Board shall not be accountable to any kind of injury/ accident at site.
15. 10% amount shall be retained as security for a period of 6 months as defect liability. In case no defect is observed the same shall be released.

Signature of the Agency with

Complete address and seal

Telephone_____

Mobile No._____

