

Gram : CENBOSEC, Delhi – 92
E-Mail: cbseedi@nda.vsnl.net.in
website: www.cbse.nic.in



Phone: 22509256-59
Fax: 22515826

CENTRAL BOARD OF SECONDARY EDUCATION

(An Autonomous Organisation under the Union Ministry of Human Resource Development Govt. of India)

"SHIKSHA KENDRA", 2, COMMUNITY CENTRE, PREET VIHAR, DELHI – 110092

F-261/Maint./LED/2013

Dt. 16.02.2013

.....
.....
.....
.....

**Sub: Limited tender for supply of LED green line and flood light luminaires
alongwith light poles**

Sir,

The Board intends to provide campus lighting whereat green line variant type luminaires pole mounted shall be installed. Simultaneously, the pole mounted flood lights luminaires shall be provided. The quantities and the specification shall be as per the schedule annexed herewith. The material is to be provided on priority basis preferably within 10 days from the date of supply order.

Agencies/authorized dealers who are interested to participate the bid may apply on the prescribed format alongwith an EMD of Rs. 15000/- payable through DD/BC/Bank Guarantee in f/o the Secretary, CBSE. Last date to submit the tender is 22.02.2013 upto 2.30 p.m. Incomplete and conditional tenders shall be summarily rejected. The Chairman, CBSE reserves the right to reject any or all the tenders without assigning any reason thereof.

Yours faithfully

(S.K. SHARMA)
Superintending Engineer

SECHDULE-I

Name of work: Supply of LED green line and flood light luminaires along with light poles

Part A: Supply of outdoor lighting luminaires

	<u>DESCRIPTION</u>	<u>UNIT</u>	<u>QTY</u>	<u>RATE</u>	<u>Amount</u>
1	Supply of Phillips make Green line outdoor lighting luminaires Variant model, Green line ,24high Power LED lumen output :3500 lm white colour, power conjunction: 45W nominal voltage: 220v-240 AC optics peanut: Driver: integral type CRI 70 mounting (OD) 28-40mm ,weight: 24kg protection IP 65,class 1 complete with all electrical circuit, CG Box etc.	Each	15		
2	Supply of Phillips make outdoor flood lighting luminaires variant model SLF 125 Type SLF125 IxSONT250W complete with all electrical circuit, CG Box etc.	Each	15		

Accepted by me

Sign. of Prop./Manager

Seal of firm

Telephone no. _____

SECHDULE-II

Name of work: Supply of poles

<u>Sl. No.</u>	<u>Description</u>	<u>Rate</u>	<u>Qty.</u>	<u>Amount</u>
<u>1</u>	Supplying & erection of 7.50 Mtr long metallic swaged steel tubular pole conforming to IS 2713 (part II) 1980. Designing 410 Sp-9 having size , bottom portion of 139.7 x 4.50 mm (length - 4.50 Mtr) middle portion of 114.30 x 3.85 mm (length 1.50 Mtr) upper portion of 88.9 x3.25 mm (length 1.50 Mtr)with detachable arm 48 mm OD x 300 mm long for fixing of street light fitting and having MS base plate 6 mm thick of size 300 mm x 300 mm welded at base i/c hole for wire entry with one No. earth stud making foundation with cement , sand, concrete 1:3:6 (1 cement ,3 coarse sand , 6 graded stone) and making cement concrete collar of size 0.40 Mtr dia x0.50 Mtr height to accommodate GI/HDPE pipe for cable entry i/c painting etc. complete as required .	Each	15	
<u>2</u>	Supplying & Fixing of 80 mm dia GI pipe (class B) pole with overall height 5.5 Mtr. complete with 300 mm x300 mm x 6 mm thick base plate i/c providing & Fixing MS angle 35x35x4 mm rectangular frame of size 750x250 mm duly curved in the center matching the pole size and fixed with capping nipple duly plugged and affixed with a conical spike at top i/c making foundation with 1:3:6 (1 cement, 3 coarse sand, 6 graded stone) of 40 mm (N.S.) and making cement concrete collar of size 0.40 Mtr. dia x 0.50 Mtr. height to accommodate GI/ HDPE pipe for cable entry i/c aluminium painting etc. complete as required.	Each	15	

Accepted by me

Sign. of Prop./Manager

Seal of firm & Telephone no. _____

Terms & conditions

1. The rates are to be quoted in words & figures without any cutting and overwriting.
2. The work shall be executed as per CPWD specifications.
3. The supplier shall be required to submit manufacturer certificate alongwith the bill.
4. The pipe shall be of Jindal make (B Class)ISI Marked.
5. Taxes if any must be clearly mentioned.
6. The pole shall have proper arrangement of fixing of MS powder coated lockable box to house MCB, neutral link and bus-bar and earth stud.
7. No escalation of rates shall be allowed.
8. No running payment shall be made, however final bill shall be paid within 15 days from the date of submission.
9. Against supply of material 75% secured advance shall be payable against submission of bank guarantee for the equivalent sum.
10. The work is time bound hence needs to be completed within stipulated time period of 15 days from the 7th day of the work order.
11. All T&P shall be arranged by the contractor.
12. The contractor shall be responsible for the safety of its workers.

Accepted by me

Sign. of Prop./Manager

Seal of firm

Telephone no.

Mobile No._____