Gram : CENBOSEC, Delhi – 92 E-Mail: cbsedli@nda.vsnl.net.in website: www.cbse.nic.in



Phone: 22509256-59 Fax: 22515826

> (S.K.Sharma) Consultant (Tech.)

CENTRAL BOARD OF SECONDARY EDUCATION

(An Autonomous Organisation under the Union Ministry of Human Resource Development Govt. of India) "SHIKSHA KENDRA", 2, COMMUNITY CENTRE, PREET VIHAR, DELHI – 110092

2.2013
18, Gurgaon.
rinkler system
gencie shaving
scribed format
evel of quality.
Delhi is to be
r duly filled in
har, Delhi-92.
ours faithfully

<u>Schedule of work</u>
Item: Modification in the fire sprinkler system including extension with flexible S.S. couplers.

SI.	Description	Qty.	Unit	Rate	Amount
No.					
1	Modification/augmentation of the existing Fire				
	Sprinkler System using flexible stainless steel				
	couplers.				
2	Dismantling of existing sprinklers at different	66	each		
	height above false ceiling using scaffolding etc.				
	after draining at the line.				
3	Dismantling of existing sprinkler distribution line	2	Job		
	size 32/25 mm through welding & shifting to new		work		
	location using old ceiling brackets through drilling				
	in the RCC slab i.e. providing extension with M.S.				
	pipe of suitable size				
4	Supply & fixing of S.S. rosset plate below false	66			
	ceiling using specified size drilling eqpt. without				
	denting/scratching the false ceiling tiles etc.				
	complete.				
5	Fixing of dismantled sprinklers on the modified				
	distribution line maintaining the symmetry with				
	the internal light fittings.				
6	Supply & fixing of 25 mm flexible stainless steel				
	304 working pressure 175 psi (12.1 bar) one piece				
	leak proof test sprinkler drop hose with socket,				
	heavy duty nipple, reducer bracket, support,				
	welding, cutting etc. as per site requirements.				
	(UL/LPC listed)				
	Length:	20			
	1000 mm	38			
	1200 mm	18			
	1500 mm	10			

Total Amount – Rs.

	Signed by
	Prop./Manager
	Seal of the Firm
Mobile/Telephone no.	

Terms &condition:

- 1. The work shall be executed as per the CPWD specification & best engg. Practice.
- 2. The material of reputed/specified brand shall only be approved; namely FlexDrop/Young JIN/HD.
- 3. The work is to be completed within 3 days from the date of the work order.
- 4. In case of delay in execution 1 % penalty per day shall be levied subject to a ceiling of 10 %.
- 5. Delays/stopping the work without valid reason, the Board shall rescind the work.
- 6. In case of poor workmanship/noncompliance of the directions of the Engineer In charge the work shall be withdrawn & got executed at the risk & cost of the defaulting agency.
- 7. No running payment/secured advance shall be paid.
- 8. The measurements shall be made on satisfactory completion of work, jointly by both i.e. agency & the Board's Engineer.
- 9. On completion the work shall be tested as per the I.S code.
- 10. The agency shall ensure adequate safety of its workers at site & in case of any accident/injury to the workmen; the Board shall not be connected in any manners.
- 11. The agency shall ensure the aesthetics of the GI perforated tiled roofing/false ceiling while drilling holes/cut out of desired size/shape.
- 12. In case of any negligence/deliberate damage to the work of other agencies, the damage/loss shall be recovered from the bill & in this regard, the decision of the Engineer In charge shall be final & binding.

Signed by Prop./Manager Seal of the Firm Mobile/Telephone no._____