CENTRAL BOARD OF SECONDARY EDUCATION

2, Community Centre, Preet Vihar, Delhi-110092

Last date of submission: 07.11.2012 Upto 2:00 p.m.

Opening of tender: 07.11.2012 at 2.30 p.m.

TECHNICAL-BID

Tender for wooden cup-board & wooden cabinet

Note:	: Tenderer must read the instructions before filling
	the particulars in this part.
1. <u>Credentials of the Tende</u>	<u>erers</u>
1.1 Name of the Agency with Regn. No.	
1.2 Office Address and Tel. No.	
1.3 Name(s) of the Proprietor/ Partners	
1.4 DVAT No	
1.5 Service Tax No.	
1.6 PAN No	
(with documentary evidence	
2. Past Experience (preferable la	st three years)
With all necessary documents	ary evidence
Such as copy of work order et	cc.

SL.	Year	Name of the	Cost of the work	Officers Concd. In	Period
No.		Organization		the Organization	From
				with T.No.	
01.	2009-2010				
02.	2010-2011				
03.	2011-2012				

2.2	Has the firm been ever debarred/Black Listed by any organization?	
	If 'Yes' the details thereof.	
	Similar work at hand in Delhi/Gurgaon/ Noida etc. and nearby cities	
2.3	Particulars of Demand Draft paid as Earnest Money:	
	Amount : 30,000/ -	
	DD NO.:	
	Issuing Bank with date of issue:	
		(Signature of the tenderer) With complete address and seal
		Tel. No. :
		Mobile No.:
		Place:
		Date :

Price-Bid

<u>Schedule</u>

SI. No	Item Description	Qty.	Rate	Amount
1.	Fabrication of wooden cub-boards with 19 mm commercial board, size 8.0'x 3.0' & depth 16" with 7 shelves (8 compartments) lamination on door shutters & corner side /endpiece with 1.0 mm thick sheet, shelves to have white colour lamination 0.7 mm thick on the top & edges. 6 mm BWR commercial ply conforming to IS: 1328 to be used in the back. Teakwood half round gola to be fixed on the exposed joinery and 6x19 mm teakwood margin affixed wherever required. The cupboard shall be aligned & enjoined together. Each wooden cup-board shall have 4 shutters of height 4.0' each fixed with ½"x ¾" s/s hinges, 4" s/s handles, magnet-catchers, tower bolts, concealed lock etc. complete. Interior wooden portions shall be coated with wood primer & painted with synthetic enamel paint of approved brand. The cub-boards shall be affixed with the existing brick walls with 50mm metallic fasteners as per directions of the Engineer-in-charge. The half round gola and other un-laminated areas shall be polished with French spirit polish with 2 or more coats including a coat of filler. Approved brands: 1. 19mm commercial board: Bhutan board(popular), Zevit, GMG, Silvertouch, Hutch, Shell 2. 6mm BWR commercial ply: GMG, Zevit, Silvertouch, GBC, Shell, Hutch 3. 1.0 mm laminated sheets: Croma, Hutch, Virgolamb, Savedecor, Greenlam, Richlam 4. 0.7 mm laminated sheets: Orpat, Safeplus, Silverline, Duke, A-one 5. Paints: Nerolac, Burger, ICI NOTE: The Board, Ply and Laminates must be ISI marked.	112 sq.mtr. OR 50 nos.	Per sq. mtr. OR Each	
2.	Providing wooden cabinet with 19 mm commercial board, back with 6mm BWR ply conforming to IS: 1328, size 3'x 8' depth 16" with 2 shelves (3 compartments) and intermediatery supports, lamination on sides & top with 1.0 mm mica sheet, shelves with 0.7			

mm laminate on top & edges. Half round gola on the front duly French polished. Interior to be applied wood primer, filler & duly painted with Synthetic ename paint. The sliding shutter with 6 mm glass, aluminium Uchannel & all requisite fittings shall be provided. The brands mentioned at SI. no. 1 shall be applicable.	1 no.	Each	
--	-------	------	--

GRAND TOTAL

With complete address and seal
Tel. No. :
Mobile No.:
Place :
Date :

TERMS & CONDITIONS

- 1. The work has to be completed within 15 days of the issue of the work order.
- 2. The work shall be executed as per CPWD specifications and best workmanship.
- 3. The selected agency shall have to executed an agreement.
- 4. The agency has to depute a Site Supervisor for coordinating and supervising the work. He must be a qualified and experienced person.
- 5. In case of delay, a penalty of 3% per week shall be levied.
- 6. In case of slow progress/ inferior workmanship/ inordinate delay, the Board shall have the right to rescind the work.
- 7. The measurements shall be made jointly.
- 8. Materials should be got approved by Engineer-in-charge before installation.
- 9. No running payment would be made. Final payment will be made within 20 days of successful completion of the work and submission of the bill duly verified by the Junior Engineer.
- 10. 10% of gross value of work done shall be retained as security against defect liability and would be released after completion of six months. Defects pointed out are to be rectified within a week.
- 11. The quantities mentioned in the schedule are tentative which may increase or decrease to any extent as per site conditions.
- 12. Any extra/ substituted item if necessitated, shall be executed only after written approval of the Engineer-in-charge. Payment would be made on analyzed rates.

	7.000р.000.00
Mobile No	0
Address:	

Seal of the Agency

Accepted be me