Gram: CENBOSEC, Delhi – 92 E-Mail: cbsedli@nda.vsnl.net.in website: www.cbse.nic.in



Phone: 22509256-59 Fax: 22515826

CENTRAL BOARD OF SECONDARY EDUCATION

(An Autonomous Organisation under the Union Ministry of Human Resource Development Govt. of India) "SHIKSHA KENDRA", 2, COMMUNITY CENTRE, PREET VIHAR, DELHI – 110092

No:F-2/01/CW/TR/	Date:21.01.2013
••••••	
••••••	
	AL.
Sub: - Limited Tender for Renovation of Toil	et Block at 8 th floor HQ bldg., Preet Vihar
Delhi-92.	

Sir,

The CBSE intends to invite Limited Tenders for renovation of toilets at 8th floor of HQ building, Preet Vihar Delhi through specialized agencies having executed minimum two similar works. Rates are to be quoted on the prescribed format annexed herewith. The agencies willing to submit tenders are advised to visit the building so that exact quantum of work is assessed. The tender complete in all respect along with an EMD of Rs. 20,000/payable in favour of the Secretary, CBSE, Delhi must be submitted latest by04.02.2013 upto 2:30 p.m. and dropped in the tender-box placed at Ground Floor near Reception Counter, CBSE HQ building, Preet Vihar, Delhi-92. Being specialized work, the successful agency shall be required to submit an affidavit ensuring guarantee against leakage of any kind in the GI/CI piping work for a period of 5 years. The tenders shall be opened on 04.02.2013 at 3.00 p.m. in the presence of the tenders who may wish to be present.

Incomplete and conditional tenders shall be summarily rejected. The CBSE reserves the right to reject any or all the tenders without assigning any reason thereof.

Yours faithfully

(S.K. SHARMA) Superintending Engineer

CENTRAL BOARD OF SECONDARY EDUCATION, 2, COMMUNITY CENTRE, PREET VIHAR, DELHI-92

Last Date for submission :04.02.2013 Upto 2.30 P.M.

Name of work: Renovation of Ladies and Gents toilet at 8th Floor, CBSE, H.Q
Building, Preet Vihar

1 Cradentials of tenderer

S.No.	Year	Name of the	Cost of the work	Officer Concd. in the	Period From	To
		Organization	(Executed)	Organization with		
				T.No.		
01.						
02.						
03.						

3.2. Present as	ssignment in hand complying tender parameters: pa	articularly in multi-
storied bldgs.	(Supported with documentary evidence)	

(i)

(ii)

(iii)

3.5 Earnest Money Deposit (EMD)

4. Particulars of D.D. as earnest money:

- 1. The Govt. Departments, Public Sector Units, Small Scale Industrial (SSI) Units (only permanently registered) & agencies registered with NSIC etc., are exempted from submitting EMD.
- SSI Units and agencies requesting for exemption from submission of EMD shall submit a copy of their Registration Certificate.
 Only such SSI Units and agencies registered for the same trade/Item for which the tender is relevant shall be exempted from submission of EMD.
- 3. EMDs of unsuccessful tenders shall be refunded after reasonable time without interest.
- 4. The tenders without EMD or partial EMD shall be summarily rejected.
- 5. Earnest money to successful tenderers shall be returned after submitting the Initial Security Deposit (ISD) @ 10% of contract value in form as prescribed under General Financial Rules, 2005. No interest will accrue on such deposit.

	•	
Amount Rs.:	20,000/-	-
D.D/B.D Nos.:		
Issuing Bank with		
Date of Issue:		_
		_
5. The Financial-Bid	of the prequalifying agencies	shall only be opened.
6. Copy of the docum	nents at Serial Nos.1.3 to 3.5	be attached.
Declaration : All term	ns and conditions as mention	ned in the tender are acceptable to me/us
		(Signature of the Tenderer) With complete address and seal
Tel. No.:		
Mobile No.:		
Place:		
Date :		

PRICE SCHEDULE

Name of work: Renovation of Ladies and Gents toilet at 8th Floor, CBSE, H.Q Building, Preet Vihar

S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
1	Dismantling Marble Flooring laid in cement mortar including stacking within 50 mt. lead	40	sqm		
2	Dismantling old wall ceramic tiles including disposal of rubbish to the dumping ground within 50 meters lead.	120	sqm		
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and buying-back the same (quoted amount shall be reduced) Of area 3 sq. meters and below	7	each		
4	Dismantling of flushing cistern of any size including stacking of useful materials near the site and disposal of unserviceable materials within 50 meters lead.	4	each		
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	150	sqm		
6	Dismantling concealed G.I. pipes including excavation, taking out the pipes, manually/ by mechanical means including buying back the same: 15 mm to 40 mm nominal bore				
		50	meter		
7	Dismantling concealed C.I. pipes including excavation, taking out the pipes, manually/ by mechanical means				
	breaking lead caulked joints and buying back the same. Up to 150 mm diameter		meter		
8	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey	120	sqm		

cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. Preferable brands: NITCO, KAJARIA, NAVIN, ORIENT, SOMANI 9 Providing and laying Polished vitrified antiskid/rustic floor tiles 500x500 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make in all colours, shades, laid on 20mm thick bed of Cement Mortar 1:4 (1 Cement: 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete. Preferable brands: NITCO, KAJARIA, NAVIN, ORIENT, SOMANI 10 Providing and fixing 35 mm thick door shutter (size 7x3 ft) with frame (size 3"X5" inches) with decorative vineer, panelling etc. including ISI marked black enameled M.S. butt hinges with necessary screws. The rate are inclusive of lamination sheet to be fixed as per directions of Engineer-incharge. Preferable brands of Board: BHUTAN, DURO, ZEVIT, GMG 11 Providing and fixing 28 mm thick door shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as styles and rails. Joints are made using solvent adhesive and GI 'C' sections (39mm x 19mm x 0.6mm thick) or M S pipe (40mm x 20mm) stiffener frame		,			
antiskid/rustic floor tiles 500x500 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS :15622 of approved make in all colours, shades, laid on 20mm thick bed of Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete. Preferable brands: NITCO, KAJARIA, NAVIN, ORIENT, SOMANI 10 Providing and fixing 35 mm thick door shutter (size 7x3 ft) with frame (size 3"X5" inches) with decorative vineer, panelling etc. including ISI marked black enameled M.S. butt hinges with necessary screws. The rate are inclusive of lamination sheet to be fixed as per directions of Engineer-incharge. Preferable brands of Board: BHUTAN, DURO, ZEVIT, GMG 11 Providing and fixing 28 mm thick door shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as styles and rails. Joints are made using solvent adhesive and GI 'C' sections (39mm x 19mm x 0.6mm thick) or M S		including pointing in white cement mixed with pigment of matching shade complete. Preferable brands: NITCO, KAJARIA,			
door shutter (size 7x3 ft) with frame (size 3"X5" inches) with decorative vineer, panelling etc. including ISI marked black enameled M.S. butt hinges with necessary screws. The rate are inclusive of lamination sheet to be fixed as per directions of Engineer-incharge. Preferable brands of Board: BHUTAN, DURO, ZEVIT, GMG 11 Providing and fixing 28 mm thick door shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as styles and rails. Joints are made using solvent adhesive and GI 'C' sections (39mm x 19mm x 0.6mm thick) or M S	9	antiskid/rustic floor tiles 500x500 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make in all colours, shades, laid on 20mm thick bed of Cement Mortar 1:4 (1 Cement: 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete. Preferable brands: NITCO, KAJARIA,	34	sqm	
shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as styles and rails. Joints are made using solvent adhesive and GI 'C' sections (39mm x 19mm x 0.6mm thick) or M S	10	door shutter (size 7x3 ft) with frame (size 3"X5" inches) with decorative vineer, panelling etc. including ISI marked black enameled M.S. butt hinges with necessary screws. The rate are inclusive of lamination sheet to be fixed as per directions of Engineer-incharge. Preferable brands of Board: BHUTAN,	2 No's	each	
insert & telescopic polymeric 'L' corners . The panel shall be filled with 3mm thick high - pressure compact laminate as per manufacturer's specifications and direction of Engineer-in-charge, cover moulding shall be provided for covering fixing screws and elegant look.(for W.C. and bathroom door shutter).The brand approved shall be "Rajshree".		shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as styles and rails. Joints are made using solvent adhesive and GI 'C' sections (39mm x 19mm x 0.6mm thick) or M S pipe (40mm x 20mm) stiffener frame insert & telescopic polymeric 'L' corners .The panel shall be filled with 3mm thick high - pressure compact laminate as per manufacturer's specifications and direction of Engineer-in-charge, cover moulding shall be provided for covering fixing screws and elegant look.(for W.C. and bathroom door shutter).The brand approved shall be "Rajshree".	8	sqm	
Providing and fixing factory made door frame (single rebate) made of solid PVC	12				

	2 22		1	1	
	foam profile with homogenous fine	30	meter		
	cellular structure having smooth outer				
	integral skin having 60mm width &				
	30mm thickness and shall be fixed to				
	wall as per instructions of engineer-in-				
	charge using 100x8 sheet metal CSK				
	screws. The approved brand shall be				
	"Rajshree".				
13	Providing and fixing water closet				
1.5	squatting pan (Indian type W.C. pan)				
	with 100mm sand cast Iron P or S trap,				
	10 litre low level white P.V.C. flushing				
	cistern with manually controlled device				
	(handle lever) conforming to IS: 7231,				
	with all fittings and fixtures complete				
	including cutting and making good the				
	walls and floors wherever required .	1	each		
	Due to conversion of the system, the				
	floor is to be raised to suitable height				
	(approx 8"-10") facilitating proper				
	installation. The nitch shall be filled				
	with khanger and flooring shall be				
	minimum 50 mm in proper slope.				
	White Vitreous china Orissa pattern				
	W.C. pan of size 580x440mm with				
	integral type foot rests. (Perry Make)				
14					
14	Providing and fixing white vitreous				
	china padestal type water closet				
	(European type W.C. pan) with seat and				
	lid, 10 litre low level white P.V.C.				
	flushing cistern with manually				
	controlled device (handle lever),				
	conforming to IS: 7231, with all fittings				
	and fixtures complete including cutting	3	each		
	and making good the walls and floors				
	wherever required:				
	W.C. pan with ISI marked white solid				
	plastic seat and lid				
	Preferable brands: PERRY, CERA,				
	HINDUSTAN				
15	Providing and fixing white vitreous				
1.5	china flat back half stall urinal of size				
	580x380x350mm with concealed C.P				
	Brass stop cock fittings, standard size				
	C.P. brass flush pipe, spreaders with				
	unions and clamps (all in C.P. brass)				
	with waste fitting as per IS: 2556, C.I.				
	trap with outlet grating and other	3	each		
	couplings in C.P. brass including				
	painting of fittings and cutting and				
	making good the walls and floors				
	wherever required				
	Preferable brands: PERRY, CERA				
16	Providing and fixing cascade type wash				
	basin 15 mm C.P. brass pillar taps,32				
	p tapo,o2		1	1	1

17	mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: cascade type white Vitreous China Wash basin with a single 15 mm C.P. brass pillar cock. Providing and fixing G.I. pipe complete with G.I. fittings and clamps, including cutting and making good the walls etc.	3	each	
	15 mm dia. nominal bore 20 mm dia. nominal bore	50 18	meter meter	
18	Providing and laying Double Flanged (screwed/ welded) Centrifugally (Spun) Cast Iron, Class B (IS: 1536): 100 mm dia C.I. Double Flanged Pipe	10	meter	
19	Providing and laying Double Flanged (screwed/ welded) Centrifugally (Spun) Cast Iron Gully trap: 100 mm dia C.I. Double Flanged trap	4 No's	each	
20	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	5	each	
21	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931-15 mm nominal bore.	2	each	
22	Providing and fixing C.P. brass angle valve of approved quality conforming to IS:8931 15mm nominal bore	15	each	
23	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with frame of approved make with impervious material backing:			
	 Rectangular shape 1200x600mm Rectangular shape 1500x450 mm Mirror of size 450x600mm as per approved sample. 	1 1 3	each each	
24	Providing and fixing C.P Brass Bottle Trap Heavy duty for Wash basin .(As per approved sample)	6	each	

		1	ı	ı	
25	Providing and fixing PTMT liquid soap container 109mm wide, 125mm high and 112mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour. weighing not less than 105 gms.	3	each		
26	Providing and fixing PTMT towel ring trapezoidal shape 215mm long, 200mm wide with a minimum distances of 37mm from wall face with concealed fittings arrangement of approved quality and colour. Weighing not less than 88 gms.	3	each		
27	Providing and fixing C.P. brass Pillar cock of approved quality conforming to IS standards and weighing not less than 400 gms. 15 mm nominal bore	3	each		
28	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	40	meter		
29	Providing and fixing KOPAL, Novatech., JINHAI quality make hand drier, no touch operating 20R Hygenic level, Fully Hygienic level, rated for continuous repeat use, time required to dry hand pair upto wrist, Half a minute for 230 volts, 1 Phase 50 HZ 15 amp AC supply with summer/ winter control. In rugged multiple staved grounded steel enclosure with one bracket for firm wall fixture, one meter sheathed 3 core flexible cable, 1- three pin 15 amp plug top.	2	each NDSR		

30	Providing and fixing 18mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for washbasin counters and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm.	2.0	sqm	
31	Extra for providing edge moulding to 18mm thick granite stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.	5	meter	
32	Granite work. Providing and fixing 18 mm thick stone slab table rubbed, edges rounded and polished of size 75x50 cm deep and 1.8 cm thick fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth.	3	each	
33	Granite Stone of approved shade. Extra for fixing marble /granite stone over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive including cleaning etc. complete.	6	meter	

2.4		l	1	
34	Extra for providing opening of required size & shape for wash basins/ kitchen sink in kitchen platform, vanity counters and similar location in marble/Granite/stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete	3	each	
35	Disposal of malba from worksite to dumping site within 5 k.m lead.	30	Cu.m	
36	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	20	sqm	
37	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. meters and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50meters lead: 1) With cement mortar 1:4 (1 cement: 4 fine sand) 2) With cement mortar 1:4 (1cement: 4 coarse sand).	5 10	sqm sqm	
38	Supply of Polished vitrified floor tiles 500x500 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in all colours, shades	5	sqm	
39	Supply of Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades	5	sqm	
40	P & F in position suspended false-ceiling system using 595mmx595mm Calcium Silicate Ceiling Tiles having 15mm Densified Edges and 100% Humidity Resistance, Incombustible as per BS 476 Part IV with thermal conductivity of 0.043 w/m KC and NRC 0.50, and approved surface design (SPINTONE) and edge profile (Tegular) placed in a suspended grid of size 600mmx500mm made from hot dipped GI Steel sections having an exposed surface capping of pre-finished baked	40	sqm	

	1	Π	I	I
	polyester painted coil wherein the main			
	tee of size			
	24mmx28mmx0.33mmx1200mm shall			
	be inserted in to slots between the main			
	tees at 600mm c/c and thereafter in			
	direction vertical so as to form a grid of			
	size 600mmx600mm resting on the			
	periphery walls on wall angles of size			
	22mmx22mmx 3000mmx0.40mm			
	thickness including providing necessary			
	opening for light fixtures, diffusers, etc			
	are to be made as per lay out and as per			
	directions of engineer incharge. The			
	main tees are to be suspended from the			
	ceiling/ soffit with the help of metal			
	dash fasteners of 6mmx50mm, soffit			
	cleats of 25mmx35mmx1.6mm and 4			
	mm dia GI wire with galvanized spring			
	steel leveling clips. The entire grid			
	system shall be designed to bear a			
	distributed load of minimum 15kg/			
	sq.m.			
	Approved brands: Armstrong or			
	equivalent			
41	P & F MS box of size 5x8 inches for			
	electrical switches duly electroplated	6	each	
42	Wiring for light/ fan/ exhaust fan/ call			
	bell/ point with 1.5 sq mm PVC			
	insulated copper conductor cable in			
	surface/ recessed PVC conduit as			
	required.			
	Short point	5	each	
	Medium point	6	each	
	Long point	8	each	
43	P & F including wiring for 3 pin 5/6	· ·	cacii	
T-3	amps socket outlet on existing			
	switchboard.	4	each	
44	P & L circuit wiring with 2x2.5 sq mm	+	Cacii	
44				
	PVC insulated copper conductor cable			
	along with one 2.24 mm dia copper wire			
	for loop earthing complete as required.	_		
4.5		5	meter	
45	Supply of Modular switches plate type			
	with 4 switches and 1 socket outlet as			
	approved by the Engr. Incharge.	4	each	
46	SITC of exhaust fan upto 300mm sweep			
	in the existing opening including			
	providing M.S. support as per site			
	requirement.	2	each	
	Approved brands: Crompton, Bajaj			

47	P&L in position R.C.C slabs of size 3.0'x2.25' and 5'x2.25' ft 50 mm thick for supporting the granite. The rates should be inclusive of centering & Shuttering etc. complete. C.C 1:2:4 Reinforcement	0.08 60	cum. kg	
48	P&F Tube light fitting with acrylic cover (1x40w) TL Make Philips/ Bajaj	3	each	
49	P&F bracket type light fitting over the stand post mirror (CFL Type) with lamp of 11/18 watts, as approved by the Engr. Incharge.	1	each	
50	Providing and fixing of following stainless steel Items 1) L-Drop (10" inch) on PVC Door shutter, with all fittings and fixtures complete.	7	each	
	2) Tower Bolt (10 ³ inch)	7	each	
51	Providing & fixing PVC pipe 110 mm for drainage/stacking purposes in the shaft Approved brands: Prakash, Tirupati, Kisan	Rate only	Per mtr.	
52	P&F P-trap 110 mm	1 no.	each	
53	P&F of PVC items 110 mm for connecting the IWC and drainage 1. Floor trap	1	each	
	2. Door-tee	1	each	
	3. Bend	1	each	

Terms & Conditions

- The work shall be executed as per the approved specifications and CPWD norms.
- 2. The work is time bound, hence time is the essence of the contract.
- 3. The work is to be completed within 2 months from 7th day of award of work.
- 4. All the materials shall be got approved from the Engineer Incharge before installation.
- 5. The sanitary ware & bathroom fittings should be of CERA, PARCO, JAQUAR, ORIENT, PERRY makes.
- 6. No T & P shall be provided by the Board.
- 7. Scaffolding shall be arranged by the Contractor.
- 8. The work shall be executed under the strict supervision of the Board's J.E/S.E.
- 9. The measurements shall be recorded jointly.
- 10. The affidavit certifying five years guarantee against leakage shall be given on Rs.10/- non-judicial stamp paper duly attested by the Notary Public.
- 11. Potable water shall only be used, in no case ground water shall be used.
- 12. In case of delay, a penalty @ 1% per week shall be levied subject to a max of 5%.
- 13. In case of poor workmanship, the Board shall have the right to rescind the contract and get the work executed through any other agency at the risk & cost of the defaulting contractor.
- 14. In case the work is kept suspended without any valid reason, the Board shall be free to get the remaining work executed through any other agency.
- 15. The contractor shall be required to provide adequate safety for its workers and the Board shall not be accountable to any kind of injury/ accident at site.
- 16. 10% amount shall be retained as security for a period of 6 months as defect liability. In case no defect is observed the same shall be released.

Accepted by me

Signature Prop. /Manager Tel. No. Mob. No.